



Speed ^{7,8} fps (m/s)	Min. Overhead (Deflector sheave in Overhead) 4	Min. Overhead (Sheave in machine room)	Pit Depth
	OH	OH	P
700 (3.5)	24'-0" (7315 mm)	22'-0" (6710 mm)	12'-0" (3660 mm)
800 (4.0)	24'-6" (7470 mm)	22'-6" (6860 mm)	12'-0" (3660 mm)
1000 (5.0)	28'-0" (8535 mm)	26'-0" (7925 mm)	16'-0" (4875 mm)
1200 (6.0)	29'-6" (8995 mm)	27'-6" (8380 mm)	19'-0" (8380 mm)

④ Designed for 8'-0" [2440] high cab. For 9'-0" [2745] high Cab, Overhead + 1'-0" [305], For 10'-0" [3050] high Cab, Overhead + 2'-0" [610]

Project : _____

Location: _____

Traction Gearless Overhead HOSPITAL TYPE Elevation View

Grøpe manufacturier d'ascenseurs



Elevator Manufacturing Group