



Speed ^{7,8} fps (m/s)	Min. Overhead (Deflector sheave in Overhead) 4	Min. Overhead (Sheave in machine room)	Pit Depth
	OH	OH	P
700 (3.5)	24'-0" (7315 mm)	22'-0" (6710 mm)	12'-0" (3660 mm)
800 (4.0)	24'-6" (7470 mm)	22'-6" (6860 mm)	12'-0" (3660 mm)
1000 (5.0)	28'-0" (8535 mm)	26'-0" (7925 mm)	16'-0" (4875 mm)
1200 (6.0)	29'-6" (8995 mm)	27'-6" (8380 mm)	19'-0" (8380 mm)

- ④ Designed for 8'-0" [2440] high cab. For 9'-0" [2745] high Cab, Overhead + 1'-0" [305], For 10'-0" [3050] high Cab, Overhead + 2'-0" [610]
- ⑤ When occupable space is below hoistway, counterweight safeties are required. Add 9,5" [240] to the hoistway size of counterweight location.
- ⑥ For duplex or triplex with rear entrance, see drawing on next page to calculate hoistway needed.
- ⑦ 1:1 Roping Factor with Gearless machine
- ⑧ 2:1 Roping Factor with Geared machine
- ⑨ Dimensional data is in accordance with ASME A17.1 and CAN/CSA B44 elevator codes.

Type of Opening	Capacity lbs (kg)	Speed ^{7,8} fpm (m/s)	Hoistway Width		Hoistway Depth HD ⁵	Platform Width PW	Platform Depth PD	Cab Inside Width CIW	Cab Inside Depth CID	Clear Opening CO
			HW ⁵	THW ⁵						
2SP	4000 (1800)	700-1200 (3.5-6.1)	8'-0" (2440)	24'-8" (7520)	9'-9" (2970)	5'-8" (1730)	8'-10 1/2" (2705)	5'-4" (1626)	7'-11" (2413)	4'-0" (1220)
2SP	4500 (2000)	700-1200 (3.5-6.1)	8'-4" (2540)	25'-8" (7825)	9'-9" (2970)	6'-0" (1830)	8'-10 1/2" (2705)	5'-8" (1727)	7'-11" (2413)	4'-0" (1220)
2SP	5000 (2250)	700-1200 (3.5-6.1)	8'-7" (2615)	26'-5" (8050)	10'-4" (3150)	6'-3" (1905)	9'-5 1/2" (2885)	5'-11" (1803)	8'-6" (2591)	4'-6" (1370)

For seismic conditions zone 2 and greater add to dimension (in)[mm]	HW	4" (100 mm)
	HD	1" (25 mm)
	HW Rear Opening	3" (75 mm)

Project : _____
 Location: _____

Traction Gearless Overhead HOSPITAL TYPE - Triplex 2-Speed Front Opening

Groupe manufacturier d'ascenseurs



Elevator Manufacturing Group